KOLAR DIVISION.

Notice, dated 6th March 1897.

It is hereby notified that a sum of Rs. 15-5-S, due to late contractor Vahab Alli for work done on Byadabale tank, Bowringpet taluk, has been placed in the Savings Bank. Any legal heirs of the deceased contractor, with a claim certificate, may apply to the Executive Engineer, Kolar division, for receiving the above sum within three months from this date; failing which, the amount will be forfeited to Government.

The 5th April 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar division, up to 25th April 1897, for restoring the Ammerahalli Tank, registered No. 771 of Kolar taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Ammerahalli Tank, registered No. 771, Kolar taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The work is to be started after acquisition of the lands by compensation.

AN APPROXIMATE ESTIMATE OF QUANTITIES FOR RESTORING AMMERAHALLI TANK, REGISTERED NO. 771 OF KOLAR TALUK.

Items.	*Per.*	*Bund.*	*Sluice.*	*Waste weir.*	*Total.*
Earthwork	C. yds.	59,893	..	..	59,893
Do	..	..	..	333	333
Old stone work	..	2,129	..	.	2,129
New stone work (½ a mile lead average) ..	,,	3,048	..	..	3,048
Bench mark stones	No.	2	.	..	2
Removing and re-fixing grade stones	,,	34	..	..	34
Grade stones new	,,	8	..	..	8
Year and register number stone	,,	1	..	..	1
Gauge stone 20' long	,,	1	..	..	1
Turfing	Sqrs.	21,563	..	..	21,563
Puddle trench	C. yds.	1,476	.	..	1,476
Filling in with good clay..	,,	1,476	..	..	1,476
Sluice repairing and providing with screw gear ..	L. S.	..	350	..	350
Brick in chunam	C. ft.	..	..	8,098	8,098
Plastering with chunam	Sqrs.	..	..	20·14	20·14
Burnt stone slabs	S. ft.	..	..	1,400	1,400
Concrete	C. ft.	..	..	875	875
Rough stone in chunam	C. yds.	..	..	49	59
Repairs to existing weir	L. S.	..	..	15	15

V. ARUNACHELLA MUDALIAR, *Offg. Exec. Engineer.*